

AIRFIELD SEVERE WEATHER ALARM SYSTEM

QUICK START GUIDE

Procedure

1. Open the power/control box and remove cables and accessories.



Unlatch the solar panel.
NOTE The solar panel will lift automatically to a 45° angle.



- 3. Align the solar panel with solar noon (point it where the sun is at about 12:30 p.m. local time).
- 4. Attach the legs to the power/control box and secure them in place with the cotter pins.
- 5. Secure the power/control box in place with weights or other method to keep it in place in high winds.
- 6. Locate the antenna components.



7. Insert the antenna mounting extension into the mounting base on the power/control box and tighten the thumbscrews.









Step 7

Step 8

Step 9

- 8. Thread the antenna cable up through the mounting tube and connect it to the antenna. Ensure the connector is tight to prevent water ingress.
- $9. \quad Insert \, the \, antenna \, base \, into \, mounting \, tube \, and \, tighten \, the \, thumb \, screws.$
- 10. Connect the coaxial antenna cable to the power/control box and tighten the connectors. Ensure the connector is tight to prevent water ingress.



LaneLight Traffic Technologies, Inc.

www.LaneLight.com

info@lanelight.com

1-866-466-4836

Power control/box assembled




11. Unfold the legs on the flasher stand unit.

IMPORTANT Ensure they lock in the open position.



- 12. Place the flasher unit facing the desired direction.
- 13. Secure the legs of the flasher unit with weights or other method to keep it in place in high winds.
- 14. Connect the cable from the flasher unit to the power/control box.




15. **IMPORTANT** Inside the power/control box, verify the fuse holders are in the OPEN position. **DO NOT REMOVE THE TAPE UNTIL INSTRUCTED**.



16. Connect the battery. Black wire to – terminal, red to +.



- 17. Inspect all connections.
- 18. Remove the tape from the fuse holders.
- 19. Close the fuse holders in the following order:
 - a. Close the fuse holder labeled **BATT**.
 - b. Close the fuse holder labeled **PANEL**.
 - c. Close the fuse holder labeled **LOAD**.



The system is now live.

20. Test system operation from the control tower.